

Representative SCS Landfill Expansion or Greenfield Projects Landfill Name	State	Waste Type	Liner Configuration (Top to Bottom)	Size (acres)
Allied Waste Industries, Southwest Regional Landfill	AZ	MSW	Geocomposite, 60 mil HDPE, Compacted Clay	240
Pinal County, Apache Junction Landfill	AZ	MSW	Geocomposite, 60 mil HDPE, Compacted Clay	80
City of San Diego, West Miramar Landfill	CA	MSW	Master Plan for Site Development	264
Cortino Landfill, Greenfield	CA	MSW	Geocomposite, 80 mil HDPE, GCL, 80 mil HDPE	100
East Lake Landfill Expansion	CA	MSW	Geocomposite, 60 mil HDPE, GCL	20
Orange County, Prima Deshecha Landfill Master Plan	CA	MSW	Master Plan for Site Development	545
Stanislaus County Fink Road Landfill Master Plan	CA	MSW	Geocomposite, 60 mil HDPE, Compacted Clay	560
Bondad Landfill, Cells 10 and 11	CO	MSW	2' Sand, 8 oz. Geotextile, 60 mil HDPE, 2' Compacted Clay	12
City of Glenwood Springs Landfill	CO	MSW	Shredded Tires in LCS, 3' Compacted Soil Liner	2.1
Southeast Landfill	CO	MSW	60 mil HDPE, Compacted Clay or GCL	60
Connecticut Resources Recovery Authority, Hartford Landfill	CT	CCR	Stone, Geotextile, 60 mil HDPE, Geocomposite, 60 mil HDPE, Compacted Clay	3
Citrus County Central Landfill Expansion, Phases 2 and 3	FL	MSW	Geocomposite, 60 mil HDPE, Geocomposite, 60 mil HDPE, Compacted Clay	12
DeSoto County, Class I Landfill, Zones 2, 3, 4, 5	FL	MSW	Geocomposite, 60 mil HDPE, Geocomposite, 60 mil HDPE, Compacted Clay	26
Escambia County, Perdido Class I Landfill Section 3C	FL	MSW	Geocomposite, 60 mil HDPE, Compacted Clay	20
Glades Landfill, Lateral and Vertical Expansions	FL	C&D	Geocomposite, 60 mil HDPE	138
Hillsborough County, Southeast Landfill, Phases IV, V, IV; Sections 1, 1, 7, 8	FL	MSW CCR	Geocomposite, 60 mil HDPE, Geocomposite, 60 mil HDPE, Compacted Clay	167

Representative SCS Landfill Expansion or Greenfield Projects Landfill Name	State	Waste Type	Liner Configuration (Top to Bottom)	Size (acres)
Homestead Landfill Vertical Expansion	FL	C&D	No Liner	45
Homestead Landfill Lateral Expansion	FL	C&D	Geocomposite, 60 mil HDPE Geomembrane	50
Medley Landfill Northwest and East Expansions	FL	MSW	Geocomposite, 60 mil HDPE, GCL, Geocomposite, 60 mil HDPE, GCL	49
Monarch Hill Landfill, Vertical Expansion	FL	C&D	No Liner	30
Monarch Hill Landfill, CDSL 2 Expansion, CDSL 3 Overlay, Northwest and East Expansions, Northeast Expansion	FL	MSW	Geocomposite, 60 mil HDPE, GCL, Geocomposite, 60 mil HDPE, GCL	162
Mount Dora Landfill, Greenfield	FL	C&D	No Liner	70
Naples Landfill, Lateral and Vertical Expansions	FL	MSW	Geocomposite, 60 mil HDPE, GCL, Geocomposite, 60 mil HDPE, GCL	284
Okeechobee Landfill, North Footprint,, East and South Expansions	FL	MSW	Geocomposite, 60 mil HDPE, GCL, Geocomposite, 60 mil HDPE, GCL	114
Okeechobee Landfill, South Footprint, Greenfield	FL	MSW	Geocomposite, 60 mil HDPE, GCL, Geocomposite, 60 mil HDPE, GCL	670
Putnam County, Central Landfill, Phase II, Cell 3	FL	MSW	Geocomposite, 60 mil HDPE, Geocomposite, 60 mil HDPE	14
SCMM Landfill, Lateral and Vertical Expansions	FL	C&D	No Liner	95
Volusia County, Class I Landfill, North and East Cell Expansions	FL	MSW	Geocomposite, 60 mil HDPE, GCL, Geocomposite, 60 mil HDPE, GCL	60
Volusia County, Class III Landfill, Cell Expansion	FL	Class III	No Liner	90
Ottumwa Midland Landfill, Lateral Expansion	IA	CCR	60 mil HDPE, Compacted Clay	
Southern Idaho Regional Solid Waste District, Milner Butte Landfill, Cell 4 Expansion	ID	MSW	18" Drainage Aggregate 16-oz. Geotextile 60 mil HDPE, GCL	9

Representative SCS Landfill Expansion or Greenfield Projects Landfill Name	State	Waste Type	Liner Configuration (Top to Bottom)	Size (acres)
Southern Idaho Regional Solid Waste District, Milner Butte Landfill, Cell 5 Expansion	ID	MSW	18" Drainage Aggregate 16 oz. Geotextile 60 mil HDPE Geomembrane Geosynthetic Clay Liner	10
Southern Idaho Regional Solid Waste District, Milner Butte Landfill, Cell 6 Expansion	ID	MSW	18" Drainage Aggregate, 16 oz. Geotextile, 60 mil HDPE, GCL	19
Southern Idaho Regional Solid Waste District, Milner Butte Landfill, Evaporation Pond Expansion	ID	MSW	18" Drainage Aggregate, 16 oz. Geotextile, 60 mil HDPE, Geocomposite, 60 mil HDPE, GCL	1.25
Barton County C&D Landfill	KS	C&D	In-situ Soil	20
Brooks Landfill C&D Landfill	KS	C&D	In-situ Soil	24.5
City of Witchita, Brooks Landfill	KS	MSW	Composite 60 mil HDPE, Compacted Clay	300
Coffey County C&D Landfill	KS	C&D	In-situ Soil	7
Linn County C&D landfill	KS	C&D	In-situ Soil	1
Reno County Landfill	KS	MSW	1' Compacted Soil, GCL, 60-mil HDPE, 18" Sand	52
Forty West Landfill, Washington County	MD	MSW	Soil Drainage Layer, 60 mil HDPE, GCL, 60 mil HDPE, Compacted Clay	189
Frederick County Landfill, Cell 2A and 2B	MD	MSW	Geocomposite, 60 mil HDPE, GCL, Geocomposite, 60 mil HDPE, GCL	29
Gibbons Road Ash Reclamation Project	MD	CCB (mine reclamation)	Geocomposite, 60 mil HDPE	85
Millersville Landfill, Cell 9	MD	MSW	Geocomposite, 60 mil HDPE, Geocomposite, 60 mil HDPE	67
Oaks Landfill Expansion, Montgomery County	MD	MSW, CCR	Geocomposite, 60 mil HDPE	20

Representative SCS Landfill Expansion or Greenfield Projects Landfill Name	State	Waste Type	Liner Configuration (Top to Bottom)	Size (acres)
Central Missouri Landfill	MO	MSW	Subtitle D with Sand and Geocomposite Options	54
City of St. Joseph, Property Landfills, Areas 1, 2, 3, Free	MO	MSW	Geocomposite, 60 mil HDPE, Compacted Clay	50
Charlotte Motor Speedway Landfill	NC	MSW	Geocomposite, 60mil HDPE, compacted soil liner	96
Lake Norman Landfill	NC	C&D	Compacted Soil Liner	32
Grand Island	NE	MSW	Subtitle D	6.5
Omaha Public Power District	NE	CCR		
Sand Point Landfill	NM	MSW	Soil Drainage Layer, 60 mil HDPE, GCL	99
Mingo Junction, Wheeling-Pittsburgh Steel Corporation, Steubenville Mill Landfill	OH	Industrial	3' Compacted Clay	30
Ross County, Mead Corporation Industrial Landfill	OH	Industrial	60 mil HDPE, Compacted Clay	90
Solid Waste Authority of Central Ohio, Franklin County Sanitary Landfill	OH	MSW	Geocomposite, 60 mil HDPE, Compacted Clay	330
Absolute Waste Solutions Landfill	OK	MSW	Subtitle D with Sand	15
American Environmental Landfill	OK	MSW	Subtitle D with Sand	152
Clinton Lewis Construction Company Landfill	OK	MSW	Subtitle D with Sand	20
Elliott Construction Company Landfill	OK	MSW	Subtitle D with Sand	18
Abilene Environmental Landfill	TX	MSW/ Industrial/ C&D	Geocomposite, 60 mil HDPE, Compacted Clay	167
Blossom Prairie Landfill	TX	MSW	Geocomposite, 60 mil HDPE, Compacted Clay	445
City of Beaumont Landfill Vertical Expansion	TX	MSW	Geocomposite, 60 mil HDPE, GCL or Compacted Clay	186
City of Brownsville Landfill	TX	MSW	Geocomposite, 60 mil HDPE, Compacted Clay or GCL	275
City of Port Arthur Landfill Vertical and Horizontal Expansions	TX	MSW	Geocomposite, 60 Mil HDPE, GCL or Compacted Clay	160

Representative SCS Landfill Expansion or Greenfield Projects Landfill Name	State	Waste Type	Liner Configuration (Top to Bottom)	Size (acres)
North County Landfill	TX	MSW C & D	3' Compacted Clay	52
Ralston Road Landfill Vertical Expansion	TX	C&D	3' Compacted Clay	55
Ponderosa Regional Landfill	TX	MSW	Geocomposite, 60 mil HDPE, Compacted Clay	499
Southern Oklahoma Regional Disposal Landfill	TX	MSW	Compacted Clay	80
Tall Pines Landfill Vertical and Horizontal Expansions	TX	C&D	3' Compacted Clay	193
Williamson County Recycling and Disposal Facility	TX	MSW	Geocomposite, 60 mil HDPE, Compacted Clay	575
Accomack County Landfill	VA	MSW	60 mil HDPE, GCL, 60 mil HDPE	5
Battle Creek Landfill, Page County, Phases I to V	VA	MSW	60 mil HDPE, Compacted Clay or GCL	67
Brunswick Landfill, Allied Waste Industries	VA	MSW Industrial	Geocomposite, 60 mil HDPE, Compacted Clay	33 24
Frederick County Regional Landfill	VA	MSW	Geocomposite, 60 mil HDPE, GCL	89
Frederick County Regional Landfill	VA	C&D	Soil Drainage Layer, 60 mil HDPE	47
Old Dominion Landfill	VA	MSW	Geocomposite, 60 mil HDPE	
Prince William County Landfill, Parts 1 and 2	VA	MSW	Geocomposite, 60 mil HDPE, GCL, Geocomposite, 60 mil HDPE, Compacted Clay	80
Rockingham County Landfill, Phase V	VA	MSW	Geocomposite, 60 mil HDPE, GCL	50
Shenandoah County Landfill, Cell I	VA	MSW	Geocomposite, 60 mil HDPE, Compacted Clay, Geogrid Reinforcement	10
Shoosmith Brothers Landfill and Quarry Fill	VA	MSW	Geocomposite, 60 mil HDPE; Concrete Pre-cast Panels on Quarry Wall	

Representative SCS Landfill Expansion or Greenfield Projects Landfill Name	State	Waste Type	Liner Configuration (Top to Bottom)	Size (acres)
LRI Landfill Cell 6 Expansion	WA	MSW	24" Drainage Aggregate, 16 oz. Geotextile, 2' Compacted Clay, 8 oz. geotextile, 6" Dewatering Layer, 8 oz. Geotextile	12
Cranberry Creek Landfill Expansion	WI	MSW	60 mil HDPE, Compacted Clay	52
Glacier Ridge Landfill Lateral Expansion	WI	MSW	12" Drainage Aggregate, 60 mil HDPE, Compacted Clay	34
Hickory Meadows Landfill Lateral Expansion	WI	MSW	12" Drainage Aggregate, 60 mil HDPE, Compacted Clay	76
Metro Landfill Northern Expansion West	WI	MSW	12" Drainage Aggregate, 60 mil HDPE, Compacted Clay	60
Orchard Ridge Landfill East Expansion	WI	MSW	12" Drainage Aggregate, 60 mil HDPE, Compacted Clay	46
Effe Central Landfill, Negev Desert	Israel	MSW and sludge	Geocomposite, 60 mil HDPE	200